



1. Substrate to minimum of 1:80 achieved falls primed as required for VCL
2. SIG D&T Vapour Control Layer
3. SIG D&T Approved Insulation bonded with IKOPro high performance PU adhesive. Boards to be primed with AH+ WP Primer and all joints to be sealed with AH+ Jointing Tape
4. AH+ Base Coat
5. AH+ Reinforcement Fabric
6. AH+ Top Coat
7. 100mm overlap of upstand Liquid & Reinforcement to Field area Liquid & Reinforcement
8. AH+ Jointing Tape
9. Min 18mm min Class 3 Plywood or OSB3 Upstand lining mech fixed
10. SIG D&T fixings
11. SIG D&T GRP Liquid Trim primed with AH+ WP Primer
12. 250mm AH+ Liquid & Reinforcement
13. Timber Facia / Wall Batten with Continuous Adhesive Bead
14. Brickwork by others

Waterproofing should be installed in accordance with BS 6229: (Current Iteration).

AH+ Primer Chart should be consulted for relevant Primer to be utilised before commencing with AH+ waterproofing.

The details shown are indicative and for approval only and do not form part of any contract.

Further information on all AH+ products and services can be obtained through the contact details printed below.



SIG Design & Technology
 Mannheim House, Gelders Hall Road
 Shepshed, Leicestershire LE12 9NH
 Tel: 0844 443 4778 Fax: 01509 505475
 Internet: www.singleply.co.uk
 Email: info@singleply.co.uk

TITLE:

AH+ PARAPET DETAIL UNINSULATED

DATE:

02.09.2019

DRAWN BY:

RH

SCALE:

NTS

DRAWING No:

AH+13warm

REVISION: