



1. Substrate to minimum of 1:80 achieved falls primed with AH+ Primer - Consult Primer Chart
2. AH+ Base Coat
3. AH+ Reinforcement Fabric
4. AH+ Top Coat
5. SIG D&T XPS Insulation
6. SIG D&T Water Control Layer
7. SIG D&T Roofdrain consisting of 3 parts:
  - 7.1. Filter textile layer bonded to upper part of the drainage/reservoir board
  - 7.2. Drainage/reservoir board
  - 7.3. Moisture retention & 300g per m2 Protection Fleece bonded to underside of the drainage/reservoir board
8. SIG D&T Intensive green roof growing medium as per Q37 Specification
9. SIG D&T Vegetation as per Q37 Specification

Waterproofing should be installed in accordance with BS 6229: (Current Iteration).

AH+ Primer Chart should be consulted for relevant Primer to be utilised before commencing with AH+ waterproofing.

The details shown are indicative and for approval only and do not form part of any contract.

Further information on all AH+ products and services can be obtained through the contact details printed below.



SIG Design & Technology  
 Mannheim House, Gelders Hall Road  
 Shepshed, Leicestershire LE12 9NH  
 Tel: 0844 443 4778 Fax: 01509 505475  
 Internet: [www.singleply.co.uk](http://www.singleply.co.uk)  
 Email: [info@singleply.co.uk](mailto:info@singleply.co.uk)

TITLE:  
**AH+ INVERTED GREEN ROOF  
 INTENSIVE**

DATE: 23.08.2019	DRAWN BY: RH	SCALE: NTS
---------------------	-----------------	---------------

DRAWING No: AH+1F inv	REVISION:
--------------------------	-----------