



1. Substrate to minimum of 1:80 achieved falls primed with AH+ Primer - Consult Primer Chart
2. AH+ Base Coat
3. AH+ Reinforcement Fabric
4. AH+ Top Coat
5. SIG D&T XPS Insulation
6. SIG D&T Water Control Layer
7. Min. 50mm thick slabs on proprietary supports
8. Min. 50mm layer of 20-40mm Rounded Washed Aggregate
9. 100mm overlap of upstand Liquid & Reinforcement to Field area Liquid & Reinforcement
10. 56mm IKO Enertherm cementitious faced insulation upstand board
11. 20mm Liquid only to waterproofing termination
12. Smoke Vent/Access Hatch by others

Waterproofing should be installed in accordance with BS 6229: (Current Iteration).

AH+ Primer Chart should be consulted for relevant Primer to be utilised before commencing with AH+ waterproofing.

The details shown are indicative and for approval only and do not form part of any contract.

Further information on all AH+ products and services can be obtained through the contact details printed below.



SIG Design & Technology  
 Mannheim House, Gelders Hall Road  
 Shepshed, Leicestershire LE12 9NH  
 Tel: 0844 443 4778 Fax: 01509 505475  
 Internet: www.singleply.co.uk  
 Email: info@singleply.co.uk

TITLE:  
**AH+ INVERTED ROOF BUILD-UP  
 SMOKE VENT/ROOF ACCESS KERB**

DATE: 02.09.2019	DRAWN BY: RH	SCALE: NTS
---------------------	-----------------	---------------

DRAWING No: AH+4H inv	REVISION:
--------------------------	-----------