



1. Substrate to minimum of 1:80 achieved falls primed with AH+ Primer - Consult Primer Chart
2. AH+ Base Coat
3. AH+ Reinforcement Fabric
4. AH+ Top Coat
5. SIG D&T XPS Insulation
6. SIG D&T Water Control Layer
7. Min. 50mm thick slabs on proprietary supports
8. 100mm overlap of upstand Liquid & Reinforcement to Field area Liquid & Reinforcement
9. Min. 50mm layer of 20-40mm Rounded Washed Aggregate
10. 56mm IKO Enertherm cementitious faced insulation upstand board
11. 20mm Liquid only to waterproofing termination
12. Metal retention clip by others
13. Coping Stone on mortar bed by others

Waterproofing should be installed in accordance with BS 6229: (Current Iteration).

AH+ Primer Chart should be consulted for relevant Primer to be utilised before commencing with AH+ waterproofing.

The details shown are indicative and for approval only and do not form part of any contract.

Further information on all AH+ products and services can be obtained through the contact details printed below.



SIG Design & Technology
Mannheim House, Gelders Hall Road
Shepshed, Leicestershire LE12 9NH
Tel: 0844 443 4778 Fax: 01509 505475
Internet: www.singleply.co.uk
Email: info@singleply.co.uk

TITLE:
**AH+ INVERTED ROOF BUILD-UP
TYPICAL PARAPET WITH COPING**

DATE: 02.09.2019	DRAWN BY: RH	SCALE: NTS
----------------------------	------------------------	----------------------

DRAWING No: AH+6B inv	REVISION:
---------------------------------	-----------