



1. Substrate to minimum of 1:80 achieved falls primed with AH+ Primer - Consult Primer Chart
2. AH+ Base Coat
3. AH+ Reinforcement Fabric
4. AH+ Top Coat
5. SIG D&T XPS Insulation
6. SIG D&T Water Control Layer
7. Min. 50mm thick slabs on proprietary supports
8. 100mm overlap of upstand Liquid & Reinforcement to Field area Liquid & Reinforcement
9. AH+ Jointing Tape
10. Galvanised Metal Closure by others - mech fixed
11. Min. 50mm layer of 20-40mm Rounded Washed Aggregate
12. 56mm IKO Enertherm cementitious faced insulation upstand board
13. 20mm Liquid only to waterproofing termination
14. Metal Cover flashing mech fixed by others

Waterproofing should be installed in accordance with BS 6229: (Current Iteration).

AH+ Primer Chart should be consulted for relevant Primer to be utilised before commencing with AH+ waterproofing.

The details shown are indicative and for approval only and do not form part of any contract.

Further information on all AH+ products and services can be obtained through the contact details printed below.



SIG Design & Technology
 Mannheim House, Gelders Hall Road
 Shepshed, Leicestershire LE12 9NH
 Tel: 0844 443 4778 Fax: 01509 505475
 Internet: www.singleply.co.uk
 Email: info@singleply.co.uk

TITLE:
**AH+ INVERTED ROOF BUILD-UP
 METAL ANGLE CLOSURE TO UPSTAND**

DATE: 02.09.2019	DRAWN BY: RH	SCALE: NTS
---------------------	-----------------	---------------

DRAWING No: AH+6L inv	REVISION:
--------------------------	-----------